

INSTALLATION PREPARATION

To ensure a smooth and efficient installation process, please review the following guidelines and ensure your space is prepared before our crew arrives.

Site Readiness

- Ensure the area is fully prepared for the installation. Any old cabinets, countertops, or other materials should be removed before our team arrives.
- Temporary sinks, cabinets and all appliances must also be removed to avoid interference with the installation process.

Site Access for Delivery & Installation

- Clear and unobstructed access from the delivery truck to the installation area is essential. Make sure walkways are free of obstacles, including furniture, debris, or any other items that could obstruct the path.
- For condo apartments, coordinate with the condo board or site superintendent for any necessary arrangements for elevator access and delivery protocols.
- If the project takes place in winter months, ensure snow is cleared and pathways are salted for the safety of the crew.

Designated Areas for Delivery

- A designated area near the installation space should be provided to stage the cabinets upon delivery. This will prevent damage during unloading and will allow the team to work efficiently.
- Adequate space should also be available for cabinet boxes to be stacked neatly without obstruction.

Cutting Area for Tools

- A designated cutting area is required for tools such as a table saw and miter saw. Ideally, this area should be sheltered from the elements (indoor or covered area).
- The cutting area should be in close proximity to the installation space but should not obstruct pathways or other work areas.

Floor Protection

- Floor protection is the client's responsibility. It is essential to prevent any damage to floors during both delivery and installation.
- Recommended materials include:
    - Heavy-duty floor covering (e.g., Ram Board)
    - Plywood sheets for high-traffic areas
    - Carpet protection film for carpeted areas

Plumbing and Electrical Setup

- If the installation involves sinks, dishwashers, or electrical appliances, ensure that plumbing and electrical setups are properly prepped and in the correct locations.
- Electrical outlets should be properly positioned per the cabinet design specifications. If any modifications to plumbing or electrical systems are required, these must be completed prior to installation.

By following these guidelines, you'll help ensure that the installation of your cabinets goes smoothly and on schedule. Thank you for your attention to detail and cooperation! If you have any questions or need assistance, please feel free to contact us.